

PORT OF JOHNSTOWN

**Track Rehabilitation on Road and Crossing
Contract NO. 322-001**

ADDENDUM #1

Issued April 25, 2024

The following modifications and clarifications are to be taken into consideration when tendering on this Contract and will form part of the Tender. When entering into the Articles of Agreement to do the work, they shall become a part thereof.

INSTRUCTIONS:

A1-1 TENDER FORM - Cover Page:

Closing Date and Time

Delete: May 10th, 2024

Add: May 13th, 2024 12:00pm

A1-2 TENDER FORM – Table of Contents

Section D- Drawings and Photographs

1. Item 2. Delete: Pictures of Road/Rail leading to 8 receiving pit.

Add: Additional Crossing on Main Entrance 42m²

A1-3 SECTION A

1. Project Identification

Tender Closing:

Delete: May 10th, 2024

Substitute: May 13th, 2024

A1-4 SECTION A

16. Schedule A- Unit Price Table

Item 1. Add: ****Note** all ties deemed fit for reuse will be deducted from final invoice by amount listed in provisional items.**

Part 1.1 Estimated Quantity Add: +42m²

Part 1.2 Estimated Quantity Delete: Part 1.2 Road: 190

PORT OF JOHNSTOWN

**Track Rehabilitation on Road and Crossing
Contract NO. 322-001**

ADDENDUM #1

Issued April 25, 2024

2. Delete: Installation of concrete drive area. All concrete edges must be tapered to meet existing concrete edges.
Add: Installation of asphalt drive area. All asphalt edges must be tapered to meet existing asphalt edges.

Part 2.1 (Crossing) Estimated quantity Add: 42m²
Part 2.2 Estimated quantity Delete: Part 2.2 (Road) 190m²

A1-5 SECTION A

Schedule B- Provisional Items

Add Item P-5: 6"X 8" X8'6" end plated hardwood ties.

A1-6 SECTION B INSTRUCTION TO TENDERERS

2- Closing Time

Delete: May 10, 2024

Add: May 13,2024

A1-7 SECTION C TECHNICAL REQUIREMENTS

SECTION C-1 GENERAL

1.1 General

1. Delete: two rails
2. Delete : as well as the truck lane containing rail into pit 8 from the probe station.
3. Add: three rails
4. Delete Photograph 2

PORT OF JOHNSTOWN

**Track Rehabilitation on Road and Crossing
Contract NO. 322-001**

ADDENDUM #1

Issued April 25, 2024

SECTION C-3 TECHNICAL

PART 1 General and Scope of Work

4.1 Scope of Work

1. Delete: and road between trackshed and probe area (see drawings). Fill with concrete to match rail and existing asphalt. Concrete to be 5000psi (35mpa) with 5-8% air entrained.

Add: Replace excavated asphalt with new. Reuse ties where applicable.

PART 2 PRODUCTS

2.2 Materials

Delete: Concrete work to meet C-1 standards

PART 3 EXECUTION

3.3 Warranty

1 Delete: Concrete

Add: Asphalt

April 25, 2024,

PORT OF JOHNSTOWN

**Track Rehabilitation on Road and Crossing
Contract NO. 322-001**

ADDENDUM #1

Issued April 25, 2024

A1-7 DRAWING AND PHOTOGRAPHS

Add:

ADDITIONAL CROSSING ON MAIN ENTRANCE 42M²



PORT OF JOHNSTOWN

**Track Rehabilitation on Road and Crossing
Contract NO. 322-001**

ADDENDUM #1

Issued April 25, 2024

Delete

~~Truck Lane with Rail—190m²~~

